

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/31/05

CORNER DESIGNATION: T3SR31E, J-23, The South one-quarter corner of Section 12.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was established by George S. Pershin under Contract No. 319 in May, 1879.

Record states: Set basalt stone, 16 x 12 x 10 on E. side, near top of ridge, for 1/4 Sec. Cor., from which:

A fir, 6 ins. diam brs. N 8° W, 34 lks. dist.

A fir, 11 ins. diam. brs. S 50° E 33 lks, dist.

MONUMENT AND ACCESSORIES FOUND: None. Corner and bearing tree accessories have been destroyed by County Road construction. County Road notes do not call this corner.

MONUMENT MARKING DETAIL:

- T3S R31E
- 1 S12
- 4 S13
- 2005
- PLS 1106

MONUMENT SET:

After diligent search, I declare this corner lost and re-established it by single proportionate measurement between the recovered Southwest and Southeast corners of Section 12. The corner position falls 2 feet West of the East edge of gravel County Road No. 1405, Yellow Jacket Road. At the corner point I drove a 5/8 by 24 inch with top 8 inches below road surface and capped with a 2 inch aluminum cap marked as shown in "Monument Marking Detail". Marked 4 new bearing trees:

A 9 inch ponderosa pine bears N 09° E, 35.3 feet scribed 1/4 S12 BT.

A 7 inch Douglas fir bears S 23° E, 19.7 feet scribed 1/4 S13 BT.

A 9 inch white fir bears S 49° W 62.7 feet scribed 1/4 S 13 BT.

A 10 inch western larch bears N 55° W 73.4 feet scribed 1/4 S 12 BT.

New bearing trees have a 3/4 inch brass washer stamped "PLS 1106" nailed to the face of blaze.

Attached bearing object signs to the new bearing trees. Set steel fence post 4 feet East of corner and attached "Witness" sign.

LOCATION AND COMMENTS: Corner falls near East edge of Yellow Jacket Road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\IN33J23

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-05

RECEIVED BY

Umatilla County Surveyor

Date 9-05

Rec'd by KK

No. 05-1166-B