


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 13, 1879, under GLO contract No. 319, as follows:



Set a basalt stone 16" x 10" x 8" in a mound of stone on the west side of a ridge and set a post for corner to sections 8, 9, 16 & 17.

Corner evidence recovered:

Found the original corner stone solidly set, with 4" protruding above the ground, in a small mound of stones. The corner stone is 16" x 12" x 9" and is plainly marked with four notches on the east edge and two notches on the north edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 26" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N36°30'E, 88.1 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S51°E, 107.9 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S44°W, 117.1 feet. This reference is west of a small creek.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N44°W, 116.7 feet. This reference is west of a farm road, east of a small creek and northwest of a spring which is on the east edge of the farm road. This corner is about 50 feet east of a farm road which is east of and runs parallel to a small creek.

I hereby certify the above corner point was perpetuated as hereon described on April 4, 1998. Magnetic declination: 18°E.



Renews June 30, 1998

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 4-98
Rec'd By KK
No. 98-72-R