

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L - 9  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 13, 1879, under GLO contract No. 319, as follows:

Set a basalt stone 14" x 10" x 5" on the east side of a ridge for the 1/4 section corner.

T3S R31E  
1/4  
S17|S16  
PLS 1636  
1998

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 14" x 11" x 6" and is faintly marked "1/4" on the west face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 18" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the digram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 24" Ponderosa Pine scribed "1/4 S16 BT" on double blazes bears N49° E, 97.4 feet. There is a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back of the tree.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S16°30'E, 77.8 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S44°30'W, 76.0 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N75°30'W, 130.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on August 19, 1998. Magnetic declination: 18° E.



Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on December 31, 1998.

RECEIVED BY  
Umatilla County Surveyor  
Date 12-98  
Rec'd By KK  
No. 98-252-R