

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/31/05

CORNER DESIGNATION: T3SR31E, N-23, The South one-quarter corner of Section 13.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was established by George S. Pershin under Contract No. 319 in May, 1879.

Record states: A fir, 14 ins. diam for 1/4 Sec. Cor.

A fir, 18 ins. diam brs. N 58° E, 31 lks. dist.

A pine 22 ins. diam. brs. S 22° E 46 lks, dist.

MONUMENT AND ACCESSORIES FOUND: Found the rotted remains of the Corner Tree, which is now a 10 foot high Douglas fir snag. Scribe marks // S are visible on weathered NE face of snag. The scribes are nearly chest high. There are also old axe marks on the tree. The snag has been burnt.

From the Corner Tree:

A burnt out root hole bears N 58° E, 20.5 feet, (31 lks).

The Corner Tree is 2 feet South of a East-West fence line. There is evidence of a old fence, (fence post nailed to down and rotted stump), South of the Corner Tree and a old fence staple on the East side of the Corner Tree. The existing North-South fence angles about 100 feet South of the Corner Tree and intersects the East-West fence line about 35 feet East of the corner.

MONUMENT MARKING DETAIL:

T3S R31E
1 S13
4 S24
2005
PLS 1106

MONUMENT SET:

Drove a 5/8 by 24 inch rebar in the center of the root crown of the Corner Tree and capped with a 2 inch aluminum cap marked as shown in "Monument Marking Detail". Marked 4 new bearing trees:

A 6 inch ponderosa pine bears N 78° W, 45.3 feet scribed 1/4 S13 BT.

A 7 inch Douglas fir bears S 58° E, 23.7 feet scribed 1/4 S24 BT.

A 9 inch ponderosa pine bears S 17° W 34.3 feet scribed 1/4 S 24 BT.

A 8 inch ponderosa pine bears S 43° W 87.1 feet scribed 1/4 S 24 BT.

New bearing trees have a 3/4 inch brass washer stamped "PLS 1106" nailed to the face of blaze.

Attached bearing object signs to the new bearing trees. Nailed a "Witness" sign to railroad tie brace post 2 feet South of the corner.

LOCATION AND COMMENTS: Corner falls on top of ridge about 15 feet East of a old road which has been fenced across.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

1N33N23

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-05

RECEIVED BY

Umatilla County Surveyor

Date 9-05

Rec'd by KK

No. 05-1166-B