


P-13

History of original corner establishment:

May 7, 1879, a Pine Post 4 inches diameter, 4 foot long was set.

B.T.'s were a 7" Fir Bears South 58° East 8 lks and a 9" Tamarack Bears West 10 lks.



Description of corner evidence found:

A 20" diameter Fir stump in fence line with scribing visible facing Northwest.

Description of monument and accessories I established to perpetuate the original location of this corner:

From the 20" diameter Fir stump North 58° West a distance of 5.28 feet (8lks). Set 2 1/2" diameter Brass Cap on 1 1/2" x 30" Galvanized Pipe set 24" in ground stamped:



B.T.'s: A 11" diameter Douglas Fir Bears South 79° East a distance of 39.73 feet scribed, 1/4 S 22 BT.

A 11" diameter Douglas Fir Bears North 44° West a distance of 37.0 feet scribed, 1/4 S 21 BT.

Trees were painted red with "Bearing Tree" and "Witness Post" signs nailed to the trees.

Trees also have Brass Washers nailed below the BT scribe stamped:



Office of..... County Surveyor..... Umatilla
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 21st day of April....., 19.. 83
 .. David H. K... .. by .. Betty J. Cook ..
 (COUNTY OFFICIAL) (DEPUTY)

83-76-R