

USDA-FOREST SERVICE

Index

File No. V-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. Sec 34

Cor.

No. NE Cor

T 3S R. 31E

R.D. Ukiah

County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM

T3S R31E  
S27 | S26  
S34 | S35



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" l. pipe protruding 6" from ground with mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 24" dia P.St.brs N32°W32.2 ft dist tagg S32°E32.2 ft dist (old BT rot.out)  
A 22" dia P.Pine brs S21°W21.7ft dist tagg N21°E32 lk dist (old BT, heal.blaze)  
A 11" dia R.Fir brs N46°E45.1 ft dist tagg N45°W68 1/2 lk dist-recent blaze.  
A 11" dia R.Fir brs S49°E19.9 ft dist tagg N47 1/2°W30 1/2 lk dist-recent blaze.  
A 17" dia R.Fir brs N41°W23.8 ft dist tagg S41°E 35 lk dist-recent blaze.

PHOTO IDENTIFICATION DATA

Photo No. 616140 380-4  
Filed At Umatilla Nat. Forest  
Object Ident. Trees  
Ident. By \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Road #5420 to road 5412-100, then West on road 5412-100 approx. 1.4 miles to E 1/4 corner then North on first road past E 1/4 cor and following the road to a gate in the fence, then North along fence approx. 1,800 ft to corner in fence in timbered flat.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

Signature

Title

Division

Headquarters

Date

7100-52-(3/68)

*William R. Wells*

PLS 1106

October 7, 1982

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post with 54-4 sign attached, South of corner.  
Standard BLM.

Cap marked:

T3S R31E  
S27 | S26  
S34 | S35  
1978

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 4 signs where needed.

Work Done By W.R. Wells Title Surveyor Date 10/7/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At Umatilla County Surveyor Office Date

REMARKS

Witnessed by: Leslie E. Wilson

Index File No.

V-17

T.

3S

R.

31E

M.

W.M.

Tract or Surv. No.

Sec 34

Cor.

NE Cor

Index File No. V-17

**CORNER RECORD (SEARCH)**

Tract or Survey No. 5-41

Cor. No. V-17

T 3S R. 31E

R.D. Ukiah


County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

Material: Basalt stone. Size: 18" x 12" x 5"  
 Ten inches above ground; good condition. Has 5 notches on north edge. Sets in north-south fence line beside large stone mound. (Mound is 4 feet in diameter, and 2 feet deep.)

2

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

A 30-inch down fir bears N20°E, approximately 53 feet. No visible scribing.  
 SE B.T. gone.

An 18-inch p.pine bears S21°W, approximately 21 feet. Closed blaze faces corner.  
 A 36-inch pine stump, very rotten, bears N34°W, approximately 32 feet. A broken off segment is clearly (cont. in block 12)

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner stone sets in north-south fence line. Follow fence north from ¼ corner between Sections 34 and 35.

See Carney Bette 7.5 minute quadrant map.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
*Signature*

6

7

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
*Agency*

8

Signature  
 T, Hollamon

Title  
 Engineering Technician

Division  
 S, O.

Headquarters  
 Date  
 November 7, 1974

7100-52  
 REV. 65 5

4

CORNER RECORD (PERPETUATION)

MONUMENT. DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

I placed blank B. T. tag on both the NW B. T. stump segment and the SW B. T.

10

Work Done By \_\_\_\_\_ Title \_\_\_\_\_ Date \_\_\_\_\_ State Registration No. or Agency \_\_\_\_\_

Certified Cor. Record Prepared ? Yes No Filed At: \_\_\_\_\_ Date \_\_\_\_\_

11

REMARKS

(Block #3, cont.)  
scribed T35, R31E, S27, B.T.

12

Index File No. T. R. M. Tract or Surv. No. Cor.

13