


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

W-16

History of original corner establishment:

None.

No record of corner establishment found in County Records.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" I. pipe 6" in the ground with mound of stone from which:

A 20" dia Tamarack bears N84°W 136.2 ft dist marked: NE 1/16 S34 BT.

A 17" dia Tamarack bears S38°W 106.3 ft dist marked: NE 1/16 S34 BT.

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 9 signs. BTs have a lower blaze, scribed BT, with a brass washer stamped PLS 1106 nailed flush.


Set steel fence posts with 54-2 signs on both and 54-9 sign on one, South and West of corner.

Used Steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 21, 1982.

Cap marked:

Witnessed by: D. L. Kaufman PLS
Robert D. English PC
Larry D. Henshaw 6 (rod man)
Leslie E. Wilson 6



**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of..... County Surveyor..... County of..... Umatilla
Oregon

State of....., I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

Daniel H. Krumbein by *Betty J. Slatt*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd By _____

No. 82-138-B