


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-13

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 319, dated March 26, 1879. The original notes state that at the corner a Fir post was set for 1/4 corner on nearly level surface from which:



- A 18" dia Fir bears East 34 lks dist.
A 7" dia Fir bears N85°W 61 lk dist.

No restoration could be found in County Records.

Description of corner evidence found:

A 23" dia Fir Stump bears N85°W 40.26 ft dist (old BT) found scribing inside healed blaze on chunk bucked off and left next to stump.
An old rotten Fir bears East 22 ft dist+ (old BT) - its original position could not be determined.

Description of monument and accessories I established to perpetuate the original location of this corner:

By using record bearing and distance from the BT Stump I set:

2 1/2" brass cap on 2 1/2" x 30" l. pipe 15" in ground with mound of stone to cap from which:

- A 9" dia Grand Fir bears N43°E 27.1 ft dist marked: 1/4 S34 BT.
A 11" dia Grand Fir bears N70°W 41.5 ft dist marked: 1/4 S33 BT.

Blaze faces and 6" bands around bearing trees are painted red. Trees tagged with 54-3 & 4 signs. New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush. Set steel fence post with 54-4 sign attached, North of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 6, 1982.


Cap marked:

Witnessed by: D.L. Kaufman PLS
R. D. English PC
L. E. Wilson
L. D. Henshaw

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106



Office of... County Surveyor... County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the 15th day of December, 1982
Ronald H. Krumbein by Betty L. Shatt (DEPUTY)

RECEIVED BY Umatilla County Surveyor
Lata
Rec'd by
No. 82-138-B