


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-15

History of original corner establishment:

None



Description of corner evidence found:

None

No record of corner establishment in County Records.

Description of monument and accessories I established to perpetuate the original location of this corner:


Set a 2 1/2" brass cap on 2 1/2" x 30" I. pipe 24" in ground with mound of earth from which:

A 10" dia Fir bears N61 1/2° W 13.3 ft dist marked: C1/4 S34 BT.
 A 9" dia Fir bears S15 1/2° E 29.3 ft dist marked: C 1/4 S34 BT.
 Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54 - 3 & 9 signs.
 BTs have a lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.
 Set steel fence post with 54 - 2 & 9 signs attached, North of corner.
 Used steel tape and magnetic compass 19 3/4° East declination. Measure to center of BTs.

Corner monumented on October 25, 1982.

Cap marked:

Witnessed by: Robert D. English P.C.
D. L. Kaufman P.L.S.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 15th day of December, 1982
David H. Krumbein by *Betsy G. Madh*
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date _____
 Rec'd by _____
 No. 82-138-B