


Index File No. Z-19

History of original corner establishment:

Corner established in November, 1878 under G.L.O. Contract. Surveyor General's notes state:

"Set stone 16"x12"x8" in ground for 1/4 sec. cor, from which 2 fir 8" in dia. North 32 lks. dist. Pine 20" in dia. S30°E 30 lks. dist."



Description of corner evidence found:

Found 18"x13"x7" basalt stone firmly set marked 1/4 on North Face and + on top. A fir 22" in dia. bears N05°W 21.7 feet. Some scribing visible. 54-3. A pine stump bears S35°E, 20.2 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At corner position set 2 1/2"x30" galvanized pipe with brass cap marked: Placed pipe 26" in the ground and placed corner stone at base. Mound of rock around. New B.T.: A fir 11" in dia. bears N75°E, 40.0 feet scribed 1/4 S35BT. Placed brass washer on BT blaze stamped PLS 1051. Placed 54-3s and 54-4s on BT's. Placed 54-4 on fence post 5' east of corner. Painted 6" red band on both blazes and.

T3S R31E
S35
1/4 ———
T4S
OR PLS 1051
1977

I hereby certify the above corner monument was re-established as herein described.

Witnesses: D.L. Landers
S. Nelson
November 8, 1977
See Record Plat for
S6, T4S, R31E, W.M.
as filed with the Umatilla
County Surveyor.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of..... County of..... Umatilla
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19 ..
..... by
(COUNTY OFFICIAL) (DEPUTY)

5-67-M
YUGPO 730.276