


History of original corner establishment.

Corner established in November, 1878 under GLO Contract. Surveyor General's notes state:

"Set stone 18x14x5 on nearly level ground for corner to Townships 3 and 4 South, Ranges 31 and 32 East from which a Tamarac 12" in dia. bears N26°E 20 lks dist. Pine 12" in dia. bears S48°E, 46 lks dist. Pine 12" in dia. bears S54°W, 40 lks dist. Fir 6" in dia. bears N42°W, 10 lks dist.



Description of corner evidence found:

Found 20"x14"x6" basalt stone completely covered by dirt. Dimly notched with 6 notches on edges. A Tamarac 21" in dia. bears N20°E, 12.5 feet with some scribing visible. No trace of other BT's.

Description of monument and accessories established to perpetuate the original location of this corner: At Corner Position:

Set 2½" x 30" galvanized pipe with brass cap marked: Set pipe 24" in the ground and placed corner stone at base of pipe.

From which: A Fir 9" in dia. bears N52°W, 43.6 feet, scribed T3S, R31E, S36 BT.

Placed 54-3s and 54-4s on trees, brass washer on BT blaze, stamped PLS 1051.

Painted 6" red band and both blazes red.

Placed 54-2s and 54-4s on fence posts 5' north and west.

I hereby certify the above corner monument was re-established as herein described.

Witnesses: D.L. Landers
S. Nelson

T3S T4S
R31E R32E
S36
OR PLS 1051
1977



November 9, 1977
See Record Plat S6, T4S, R32E., W.M.,
as filed with the Umatilla County Surveyor.

Office of..... County of..... Umatilla
State of..... Oregon
I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)