

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


A-17  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin in May, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 14" x 10" x 8", marked with 6 notches on the south and 2 notches on the east edge, from which:

- A 18" pine bears S42°E, 125 links (82.5 feet).
- A 8" pine bears S40°W, 42 links (27.72 feet).



Corner evidence recovered:

Found the original corner stone loosely set in an east-west fence line. The corner stone is 13" x 9" x 8" and is plainly marked with 6 notches on one edge and 2 notches on another, from which:

A down and decayed Ponderosa Pine with full scribes visible for section 3, exact size indeterminate, but around 8". Root hole bears S40°W, 27.72 feet.

Nothing remains of the original bearing tree to the southeast.

Monument and accessories established to perpetuate the original position of this corner:

At the position of the original corner stone, I set a 1" x 30" iron pipe 25" into the ground. I bury the corner stone along the northwest side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

- A 17" Douglas-fir, scribed "R32E BT", bears N35°E, 26.3 feet.
- A 12" Ponderosa Pine, scribed "T3S R32E S2 CC BT", bears S10°E, 42.3 feet.
- A 16" Douglas-fir, scribed "T3S R32E S3 CC BT", bears S41°30'W, 8.3 feet. This tree has a "Witness Point" sign nailed to the back.
- A 13" Douglas-fir, scribed "T2S BT", bears N52°W, 27.4 feet.

All four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes. The remains of the original bearing tree also have a "Bearing Object" sign nailed to it.

I hereby certify the above corner point was perpetuated as hereon described on July 18, 1999. Magnetic declination: 18°E.

  
*Dennis L. Gaylord*  


Renews June 30, 2001  
Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1999.

**RECEIVED BY**

Umatilla County Surveyor  
Date 8-99  
Rec'd By AK  
No. 99-137-R