

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 21
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 18, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 18" x 10" x 8", on west slope, marked with 6 notches on south and one notch on east edges, from which:

A 11" pine bears S86°W, 78 links (51.48 feet).
No tree to the south east. Raise a mound of stones.

Corner evidence recovered:

Found the original corner stone lying loose on the ground, having slid downhill (west) about 3 feet. The corner stone is 15" x 10" x 8" and is plainly marked with six notches on one ~~edge~~ and one notch on another. A 27" Ponderosa Pine with a previously opened blaze with scribes visible, bears S86°W, 51.5 feet. A 25" Ponderosa Pine with a healed blaze, resembling an original bearing tree blaze, bears N86°W, 31.1 feet. This may be an unrecorded original bearing tree.

Monument and accessories established to perpetuate the original location of this corner:

At record bearing and distance from the original recorded bearing tree, I set a 1" x 30" iron pipe 23" into the ground. I bury the corner stone to the east of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

- A 13" Douglas-fir scribed "S34 BT" bears N13°30'E, 50.8 feet.
- A 25" Ponderosa Pine scribed "T3S R32E S1 CC BT" bears S4°30'E, 89.0 feet.
- A 10" Douglas-fir scribed "T2S BT" bears N2°30'W, 51.5 feet.

All five bearing trees described above have a "Bearing Object" sign nailed above the blazes. The three new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B". The bearing tree to the northeast has a "Witness Post" sign nailed to the back.

I hereby certify the above corner point was perpetuated as hereon described on October 8, 1999. Magnetic declination: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on 15 October, 1999

RECEIVED BY
Umatilla County Surveyor
Date 10-99
Rec'd By KE
No. 99-214-R