

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 21  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 18, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 12" x 8" x 7", on a west slope, marked "1/4" on west face, from which:

- A 14" fir bears S40°E, 37 links (24.42 feet).
- A 7" pine bears N38°W, 7 links (4.62 feet).



Corner evidence recovered:

The original pine bearing tree is a recently up-rooted, 16" Lodgepole Pine. When this tree tipped over, it moved the original corner stone with the root wad. The corner stone is lying loose on the ground. The corner stone is 13" x 11" x 7" and is plainly marked "1/4" on one face and "WCS 1907" on another face. I open the healed blaze on the original Lodgepole Pine bearing tree and find scribes, "1/4", visible. The original fir bearing tree is gone.

Monument and accessories established to perpetuate the original position of this corner:

At record bearing and distance from the center of the root hole left by the up-rooted original Lodgepole Pine bearing tree, which is N38°W, 4.6 feet, I set a 1" x 30" iron pipe, in the southeast edge of the root hole, 28" into the ground. I bury the corner stone along the southwest of the pipe. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

- A 15" Englemann Spruce, scribed "1/4 S1 BT", bears N27°30'E, 34.8 feet.
- A 16" Western Larch, scribed "1/4 S1 BT", bears S87°E, 57.9 feet.
- A 5" Lodgepole Pine, scribed "1/4 S2 BT", bears S68°W, 22.7 feet.
- A 12" Englemann Spruce, scribed "1/4 S2 BT", bears N19°W, 38.0 feet.

All four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes. The Western Larch bearing tree has a "Witness Post" sign nailed to the back.

I hereby certify the above corner point was perpetuated as hereon described on October 8, 1999. Magnetic declination: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on 15 October, 1999.

RECEIVED BY  
 Umatilla County Surveyor  
 Date 10-99  
 Rec'd By KK  
 No. 99-215-2