

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 11
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 26, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 17" x 10" x 5", 12" into the ground on northwest slope for 1/4 section corner, marked 1/4 on west face, from which:

T3S R32E
1/4 S4
S9
PLS 1636
1998

A Pine, 18" in diameter, bears N76°W, 25 links (16.50 feet), marked "1/4S BT".

A Pine, 36" in diameter, bears S76°E, 47 links (31.02 feet), marked "1/4S BT".

Corner evidence recovered:

The original corner stone is solidly set with 5" protruding above ground. The stone is 16" x 9" x 4" and is plainly marked "1/4" on the west face, from which:

A 36" Ponderosa Pine snag, 12 feet high, with scribes "1/4S BT" visible on partly healed double blazes bears S78°E, 31.0 feet.

A 22" sawn and decayed Ponderosa Pine stump with scribes "BT" visible bears N76°W, 17.5 feet.

Monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe, 27" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the northwest side of the pipe, from which:

A 9" Douglas-fir scribed "1/4 S4 BT" bears N48°E, 45.7 feet.

A 8" Ponderosa Pine scribed "1/4 S9 BT" bears S27°30'E, 14.7 feet.

A 14" Ponderosa Pine scribed "1/4 S9 BT" bears S26°30'W, 34.1 feet.

A 17" Douglas-fir scribed "1/4 S4 BT" bears N53°30'W, 21.9 feet.

The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back side of the tree. The two original bearing tree remnants also have a "Bearing Object" sign nailed to them.

I hereby certify the above corner point was perpetuated as hereon described on April 9, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylor

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Review June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY

Umatilla County Surveyor

Date 4-98

Rec'd By AK

No. 98-24-R