


History of original corner establishment:

Corner originally established in May, 1882, by George S. Pershin under GLO contract number 430, as follows:

Set a basalt stone, 18" x 9" x 6", 12" into the ground on steep S.W. slope for corner to sections 3, 4, 9 and 10 marked with 5 notches on S and 3 notches on east edges, from which:

A 7" Pine bears S74°W, 106 links (69.96 feet).  
A 11" Pine bears N45°W, 97 links (64.02 feet).  
No trees to east. Raised a mound of stones alongside.



Description of corner evidence found:

Found a 5 foot steel fence post at corner point set in a mound of stones. An old iron wagon brake handle 3 feet long is lying alongside the stone mound. No marked stone was found. From which:

The original 7" Pine is a 21" Ponderosa Pine with scribes, "32ES", visible on a previously opened blaze. Bears S75°W, 70.00 feet.

The original 11" Pine is a down 21" Ponderosa Pine with scribes, "32ES4" visible on a previously opened blaze. Root hole bears N46°W, 64.00 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

Moving the fence post aside, I set in it's place a 1 1/2" x 30" iron pipe, 22" into the ground. I bury the iron brake handle horizontally along the northeast side of the pipe. I reset the fence post alongside the iron pipe and build up the mound of stones around the pipe. A 2 1/2" brass cap attached to the Iron pipe is marked as shown in the diagram above, from which:

A 23" Ponderosa Pine, scribed "T3S R32E S4 BT" on double blazes, bears N82°W, 112.1 feet. A 3/4" brass washer, marked "PLS 1636", is nailed flush to the lower blaze.


A 5/8" x 24" Iron rod set 21" into the ground, with a 3/4" brass washer marked "PLS 1636" tied to it, bears N24°E, 43.7 feet.

A 5/8" x 36" Iron rod set 34" into the ground with a 1 1/2" aluminum cap attached, marked "S10 LS 1636", bears S38°30'E, 34.7 feet.

The three bearing trees have witness point signs nailed above the blazes.

I hereby certify the above corner point was perpetuated as hereon described on June 11, 1995. Magnetic declination: 20°E.

Office of... COUNTY SURVEYOR... County of... UMATILLA  
State of... OREGON... I hereby certify that the within instrument was filed in this office  
for record on the... day of... , 19...  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)



Renew 6/30/95

RECEIVED BY  
Umatilla County Surveyor  
Date 6-95  
Rec'd By KK  
No. 95-107-R