

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 17  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin on May 19, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 17" x 14" x 4", 12" in ground on west slope for corner to sections 2, 3, 10 and 11, marked with 5 notches on south and 2 notches on east edges, from which:

T3S R32E  
S3|S2  
S10| S11  
PLS 1636  
2002

- A 12" pine, marked "T3S R32E S2 BT", bears N43° E, 33 links (21.78 feet).
- A 32" pine, marked "T3S R32E S11 BT", bears S34° E, 16 links (10.56 feet).
- A 15" pine, marked "T3S R32E S10 BT", bears S40° W, 21 links (13.86 feet).
- A 11" pine, marked "T3S R32E S3 BT", bears N38°W, 19 links (12.54 feet).

**Original corner evidence recovered:**

The corner area has been badly disturbed by intensive logging and fence building. I recovered a decayed Ponderosa Pine stump with a blazed face with scribes "T3S R32E S11" clearly visible. A lower blaze has the scribes decayed away. A location tag was found nailed to a piece of pine stump lying loose on the ground. No other evidence of the corner or accessories remain.

**Monument and accessories established to perpetuate the original position of this corner:**

At the record bearing and distance of N34° W, 10.6 feet from the recovered original bearing tree remains, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. I build a mound of stones around the pipe. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

- A 8" Douglas-fir, scribed "T3S R32E S2 BT", bears N5° 30'E, 18.4 feet.
- A 7" Ponderosa Pine, scribed "T3S R32E S11 BT", bears S23°E, 46.9 feet.
- A 14" White Fir, scribed "T3S R32E S10 BT", bears S6° 30' W, 17.3 feet.
- A 11" Ponderosa Pine, scribed "T3S R32E S3 BT", bears N73° W, 13.2 feet.

The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower blaze, and have a "Bearing Object" sign nailed above the blazes. The bearing tree to the southwest also has a "Witness Point" sign nailed to the back side of the tree.

I hereby certify the above corner point was perpetuated as hereon described on December 3, 2002. Magnetic declination set in compass: 18°E.

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 2-03  
Rec'd By KK  
No. 03-12-R