

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G - 9  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 26, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 12" x 10" x 5", 8" into the ground on east slope for 1/4 section corner marked "1/4" on west face, from which:

T3S R32E  
1/4  
S8+S9  
PLS 1636  
1999

A 28" pine, marked "1/4S BT", bears N85°E, 64 links (42.24 feet).  
A 10" pine, marked "1/4S BT", bears N31°W, 62 links (40.92 feet).

Original corner evidence recovered:

Found the original corner stone solidly set in a small mound of stones. Corner stone is 12" x 10" x 4" and is marked "1/4", from which:  
A broken, burnt and shattered Ponderosa Pine stump, 10 feet high, with no remaining marks, bears N87°E, 42.2 feet. A sawn 24" Ponderosa Pine stump with a healed blaze bears N29°W, 40.9 feet. I open blaze to scribes "BT". A long butt lying alongside this stump has a healed blaze. I open the blaze on this long butt to scribes "1/4 S".

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 26" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I place the original corner stone alongside the pipe and build a mound of stones around the pipe, from which:

A 9" Western Larch, scribed "1/4 S9 BT", bears N75°E, 31.9 feet.  
A 11" Douglas-fir, scribed "1/4 S9 BT", bears S36°30'E, 24.5 feet.  
A 9" Douglas-fir, scribed "1/4 S8 BT", bears S59°W, 21.8 feet.  
A 13" Ponderosa Pine, scribed "1/4 S8 BT", bears N78°30'W, 27.6 feet.

Both of the original bearing tree stumps have a "Bearing Tree" sign nailed to them. The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes. The new bearing tree to the northwest has a "Witness Post" sign nailed to the back.

I hereby certify the above corner point was perpetuated as hereon described on October 25, 1999. Magnetic declination: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on October 26, 1999.

RECEIVED BY  
Umatilla County Surveyor  
Date 10-99  
Rec'd By KK  
No. 99-262-R