

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 11
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 25, 1882, under GLO contract No. 430, as follows:

Set a basalt stone 12" x 8" x 7", 8" into the ground, on a steep east slope, for 1/4 section corner, marked "1/4" on north face, from which:

- A 10" fir, marked "1/4S BT", bears N41°W, 32 links (21.12 feet).
- A 14" fir, marked "1/4S BT", bears S42°W, 69 links (45.54 feet).

T3S R32E
1/4 S9
S16
PLS 1636
1999

Original corner evidence recovered:

The original corner stone is gone. The corner point falls in a logging skid road on a very steep east slope. The original bearing tree to the northwest is a sawn 27" Ponderosa Pine stump, 5 feet tall. This stump has double healed blazes. I open the upper blaze to scribes, "1/4S". The original bearing tree to the southwest is gone.

Monument and accessories established to perpetuate the original location of this corner:

Measuring record bearing and distance from the one remaining bearing tree stump, (S41°E, 21.1 feet) I set a 1" x 30" iron pipe, 24" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I build a mound of stones around the pipe, from which:

- A 15" Ponderosa Pine, scribed "1/4 S9 BT", bears N33°E, 27.1 feet.
- A 16" Ponderosa Pine, scribed "1/4 S16 BT", bears S29°30'E, 26.4 feet.
- A 16" Ponderosa Pine, scribed "1/4 S16 BT", bears S53°W, 31.5 feet.
- A 10" Douglas-fir, scribed "1/4 S9 BT", bears N32°W, 44.0 feet.

The original bearing tree stump has a "Bearing Tree" sign nailed to it. The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes. The new bearing tree to the northeast has a "Witness Post" sign nailed to the back.

I hereby certify the above corner point was perpetuated as hereon described on October 25, 1999. Magnetic declination: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on October 26, 1999.

RECEIVED BY
Umatilla County Surveyor
Date 10-99
Rec'd By KK
No. 99-263-R