


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-18

History of original corner establishment:
Corner not previously established.



Description of corner evidence found:
Corner not previously established.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap stamped as shown in the diagram above. Set pipe 26" into the ground.

Placed a 3' diameter collar of stone around the monument and set a steel fence post 5' west of the monument with Forest Service Land Survey Monument and Property Boundary signs attached. The bearings are true. Scribed W1/16 S11 BT on a 15" White Fir which bears N64° 57'W, 36.6'. Scribed W1/16 S14 BT on a 8" White Fir which bears S54°04'W, 19.1'. The bearings are true. Each scribe is in a 24" blaze. Nailed an aluminum washer stamped RLS 852 between the letters B and T on each tree. Painted a 6" red band around the new bearing trees and attached Forest Service Land Survey Monument and Bearing Tree signs.

I certify the above corner point was perpetuated as hereon described on October 26, 1987.

Witness: Wilma Nell Haddock, Survey Aide

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1968
DAVID L. HADDOCK
852

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 23 day of November, 1987
David H. Klein by _____
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 12-87
Rec'd By [Signature]
No. 87-68-B

★ GPO—798-276