


History of original corner establishment:

Corner originally established by George S. Pershin on May 17, 1882 under contract No. 430 as follows:
 Set a basalt stone 20" x 12" x 5" in a mound of stone in an open glade on level marked with 4 notches on the south and 1 notch on the east edges from which:
 A 32" Pine bears S 23°E, 133 links (87.78 feet) marked T3S R32E S13 BT.
 A 28" Pine bears N 77°W, 183 links (120.78 feet) marked T3S R32E S11 BT.
 No other trees available.



Description of corner evidence found:

By reference from the original bearing tree evidence, I find the corner point falls in a large mound of stones in a fence corner. Fences extend north and west from the corner. There are several stones in the mound of record size, but I am unable to identify a marked stone. From the corner point:
 A broken and decayed Ponderosa Pine stump, with the decayed remains of the tree lying alongside with scribe "B" visible, bears N77°W, 120.8 feet.
 A root hole, with the decayed Ponderosa Pine lying alongside with scribes "T3S R32E S" visible, bears S20°E, 87.8 feet.


Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner position as determined by reference from the original bearing trees, I set a 2 1/2" x 30" aluminum pipe, with a 2 1/2" aluminum cap attached, 15" into the ground. The cap is marked as shown in the diagram. I build a mound of stones around and over the capped pipe, from which new bearing trees:

- A 13" Ponderosa Pine bears N68°W, 47.9 feet scribed "T3S R32E S11 BT" on a single blaze.
- A 17" Douglas Fir bears N11°E, 22.1 feet scribed "T3S R32E S12 BT" on a double blaze.
- A 24" Ponderosa Pine bears S36°E, 104.6 feet scribed "T3S R32E S13 BT" on a single blaze.
- A 16" Ponderosa Pine bears S63°W, 92.6 feet scribed "T3S R32E S14 BT" on a single blaze.

Each new BT has a 3/4" brass washer, marked "PLS 1636", nailed flush to the blaze in the scribed "B", and a "bearing tree" and "Attention" sign nailed above the blaze.

I hereby certify this corner position was perpetuated as hereon described on June 9, 1987. De: 10°E. This declination is affected by the close proximity of fence wires, which are about 4" from my compass. Witness: Warren McCann



Office of County Surveyor..... County of Umatilla
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 29th day of June, 1987
 by Dennis L. Gaylord (COUNTY OFFICIAL) by Kathleen Amodeo (DEPUTY)

RECEIVED BY

Umatilla County Surveyor
 Date 6-87
 Rec'd by KA
 No. 87-27-R