

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-5


History of original corner establishment:

The original corner was established by George S. Pershin under Contract No. 430 on May 25, 1882, as follows:

Intersect west boundary 12.32 chains north of corner to sections 12 and 13 and set a basalt stone 12" x 8" x 7", 8" into the ground on west slope for corner to sections 8 and 17, marked with 4 notches on the south and 5 notches on the east edges, from which:

A 13" pine bears N18°E, 65 links (42.90 feet) marked T3S R32E S8 BT.

A 22" pine bears S80°E, 11 links (7.26 feet) marked T3S R32E S17 BT.



Description of corner evidence found:

I determine the corner position by reference from the original bearing trees. The corner stone is gone. The original bearing tree evidence recovered is:

A 14" sawn Ponderosa Pine stump with scribes "T3S R32E S8 BT" visible on double blazes bears N9°E, 42.9 feet.

The center of a well defined root hole, with a down 24" Ponderosa Pine lying alongside on a blazed and scribed face, bears S70°E, 7.3 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner position as determined by record distance from the original bearing trees, I set a 1 1/2" by 30" galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram. From which new bearing trees:


A 7" Ponderosa Pine bears S28°E, 32.5 feet scribed "T3S R32E S17 CC BT" on a single blaze.

A 20" Douglas Fir bears N30°E, 16.3 feet scribed "T3S R32E S8 CC BT" on a single blaze.

Both new bearing trees have a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower portion of the blaze, and a "Umatilla County Bearing Object" sign nailed above the blaze.

I set a 5 foot metal fence post 2 feet east of the corner with a "Umatilla County Witness Post" sign attached.

I hereby certify the above corner position was perpetuated as hereon described on July 2, 1987. De: 20°E. Witness: Steven J. Scritchfield.



Office of... County Surveyor..... County of... Umatilla  
 State of... Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the... 4... day of... August... 1987.  
 David H. K... by..... (DEPUTY)  
 (COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor  
 Date 8-87  
 Rec'd by RA  
 No. 87-15-R