


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-7

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 1882. The original notes state that at the corner a 15" x 10" x 5" basalt stone was set 10" in ground on SW slope marked: 1/4 on North face, from which:



A 10" dia Pine bears N9°W 211 lks dist.  
A 20" dia Tamarack bears S38°W 90 lk dist.

Remonumentation was done in 1977 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" l. pipe 15" out of ground in mound of stone from which:

A 24" dia Ponderosa Pine bears N8½°W 139.0 ft dist tagged S9°E 211 lk dist (old BT healed blaze)  
A 26" dia Tamarack bears S39°W 58.6 ft dist tagged N38°E 90 lk dist (old BT open blaze) with visible scribing.


Description of monument and accessories established to perpetuate the original location of this corner:

Set steel fence post with 54-2 and 4 signs West of corner.  
Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54-3 and 4 signs.  
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner maintained on October 4, 1982.

Cap is standard BLM. Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of.....County Surveyor..... County of.....Umatilla

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 15<sup>th</sup> day of December, 1982

*David H. Krumbein* by *Betty J. Shatto*

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY  
Umatilla County Surveyor ☆ GPO—798-276  
Date \_\_\_\_\_  
Rec'd by \_\_\_\_\_  
No. 82-137-B

History of 1977 BLM Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of secs. 17 and 20, determined at record bearing and distance from the original bearing trees:

A Pine, 23 ins. diam. bears N 9° W., 211 lks. dist., with healed blaze.

A Larch, 25 ins. diam., bears S 38° W., 90 lks. dist. with scribe marks  
1/4 S visible on partially healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 18 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S R32E  
1/4 S17  
S20  
1977

RECEIVED BY

Umatilla County Surveyor

Date \_\_\_\_\_

Rec'd by \_\_\_\_\_

No. 82-137-B