


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-13

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, dated May 1882, under Contract No. 430. The original notes state that at the corner position a 4" x 4" x 4" wooden post was set 2 ft in ground on steep North slope marked with 2 notches on South edge, 3 notches on East edge, and T3S S22 on Northeast; R32E S27 on Southeast; S28 on Southwest; and S21 on Northwest edges from which:



- A T. 12" dia. bears N45°E 29 lks dist marked: T3S R32E S22 BT.
- A 9" dia. Fir bears S72°E 41 lks dist marked: T3S R32E S27 BT.
- A 7" dia T. bears S55°W 18 lks dist marked: T3S R32E S28 BT.
- A 5" dia Pine bears N56°W 13 lks dist marked: T3S R32E S21 BT.

Remonumentation was done in 1977 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" x 28" l. pipe set 26" in ground from which:

- A 16" dia. Tamarack bears S55°W 11.0 ft dist tagged N55°E 18 lk dist (old BT) healed blaze.
- A 8" dia. Fir bears N34°W 18.0 ft. dist. tagged S35°E 29 1/2 lk dist - recent blaze.
- A 9" dia. Fir bears N56°E 20.8 ft dist tagged S56°W 32 lk dist - recent blaze.
- A 9" dia. Fir bears S62°E 27.0 ft dist tagged N60°W 42 lk dist - recent blaze.

Description of monument and accessories established to perpetuate the original location of this corner:


Set steel fence post with 54-4 sign on section line near corner. Tagged trees with 54-3 and 4 signs as needed.

6" band around bearing trees and blaze faces are painted red.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of trees.

The corner was maintained on September 23, 1982 Cap is standard BLM. Cap marked:

Witnessed by : D.L. Kaufman PLS



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of... County Surveyor... County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office
for record on the 15th day of December 1982
David H. Lumbert by Betty Shatto
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date
Rec'd By
No. 82-136-B

History of 1977 BLM Remonumentation - (From BLM Field Notes)

The cor. of secs. 21, 22, 27, and 28, determined at record bearing and distance from the only remaining original bearing tree:

A larch, 16 ins. diam., bears S. 55° W., 18 lks. dist., with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2 ½ ins. diam., 22 ins. in the ground, and in a mound of stone, 2 ft. base, to top, with brass cap marked:

T3S	R32E
S21	S22
S28	S27
1977	

from which new bearing trees

A Grand Fir, 9 ins. diam., bears N. 56° E., 32 lks. dist., mkd.
T3S R32E S22 BT.

A Grand Fir, 10 ins. diam., bears S. 60° E., 42 lks. dist., mkd.
T3S R32E S27 BT.

A Grand Fir, 9 ins. diam., bears N. 35° W., 29½ lks. dist., mkd.
T3S R32E S21 BT.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-136-B