


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-15

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner a 18" x 12" x 5" basalt stone was set 12" in ground on steep West slope marked 1/4 on the North face from which:



A 12" dia. Tamarack bears N50°W 21 lks dist. marked: 1/4 S BT.
A 10" dia. Fir bears S46°E 18 lks dist. marked: 1/4 S BT.

Remonumented in 1977 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" x 28" l. pipe set 26" in ground from which:


- A 20" dia. Fir bears S45°E 10.0 ft. dist. (free down-headed blaze).
- A 16 1/2" dia. red Fir bears S45°E 28.8 ft dist tagged N45°W 43 lk dist. (recent blaze).
- A 12" dia. Red Fir bears N56 1/2° W 26.3 ft dist tagged S56°E 40 1/2 lk dist (recent blaze).

Description of monument and accessories established to perpetuate the original location of this corner:

Set steel fence post with 54-4 sign on section line near corner.
Painted 6" band around bearing trees and blaze faces red. Tagged trees with 54- 3 and 4 signs where needed.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

This corner was maintained on September 23, 1982. Cap is standard BLM. Cap marked:

Witnessed by: D. L. Kaufman PLS



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 15th day of December, 1982
David H. Drumblin..... by Betty L. Shatto
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-136-B

History of 1977 BLM Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of secs. 22 and 27, monumented with the original basalt stone, 18 x 12 x 5 ins., firmly set 10 ins. in the ground, mkd. 1/4 on N. face, from which the remains of the original bearing trees:

A decayed Larch Stump, size indeterminate, bears N. 50° W., 18 lks. dist., no marks visible. (Record, 21 lks.)

A root hole, bears S. 46° E., 18 lks. dist., with a down fir alongside, 20 ins. diam., with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap marked:

T3S R32E
1/4 S22
S27
1977

from which new bearing trees

A Grand Fir, 11 ins. diam., bears N. 56° W., 40½ lks. dist., mkd. 1/4 S22 BT.

A Grand Fir, 14 ins. diam., bears S. 45° E., 43 lks. dist., mkd. 1/4 S27 BT.

Deposit corner stone alongside iron post.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-136-B