


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-5

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated in May 1882. The original notes state that at the corner position a 5" x 4" long wooden post was set 2 ft in ground, faced on NE and SE edges marked: R32E S20 on NE and T3S R32E S29 on SE edge from which:



A 10" dia Fir bears N76°E 75 lk dist.  
A 16" dia Pine bears S38 E 83 lk dist.

No restoration appears in County Records.

Description of corner evidence found:

A 25" dia Red Fir bears N78°E 49.5 ft dist tagged S76°W 75 lk dist (old BT dead, healed blaze).  
A 28" dia P. Pine bears S40°E 54.8 ft dist tagged N38°W 88 lk dist (old BT open blaze with visible scribing)

Description of monument and accessories I established to perpetuate the original location of this corner:


I reset the closing corner using distance-distance intersections from existing bearing trees. This corner is 8.17' W. of the range line common to T3S R31 and 32E. I set a 3" brass cap on 2 1/2" x 30" l. pipe 24" in the ground with mound of earth from which:

A 10" dia Red Fir bears N65°E 9.6 ft dist marked: T3S R32E S20 CC BT.  
Blaze faces and a 6" band around bearing trees was painted red. Trees tagged with 54-3 and 4 signs where needed and new BT has a lower blaze marked BT with brass washer stamped PLS 1106 nailed flush. Set steel fence post with 54-4 sign North of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on September 27, 1982.

Cap marked:

Witnessed by: D.L. Kaufman PLS



REGISTERED PROFESSIONAL LAND SURVEYOR

*William R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of.....County Surveyor..... County of.....Umatilla

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 27 day of December, 1982

*David H. Kaufman* *Billy L. Shatto*  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY W GPO-798-276

Umatilla County Surveyor

Date \_\_\_\_\_

Rec'd .y. \_\_\_\_\_

No. 82-137-B