


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

S-15

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 16" in ground with mound of stone to cap, from which:

A 12" dia. red fir bears N66°W - 24.2 ft. dist. marked: CN 1/16 S27 BT.

A 13" dia. P. Pine bears S34°W-31.1 ft. dist. marked: CN 1/16 S27 BT.

Set steel fence posts, with 54-2 signs and 1 54-9 sign, South and East of and near corner.


Painted 6" band around bearing trees and blaze faces red. Tagged trees w/54-3 & 9 signs. New BTs have lower blaze scribed BT with brass washer stamper PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination.

Measured to center of BTs.

Set corner on October 14, 1982.

Cap marked:



Witnessed by: Leslie E. Wilson
Larry Henshaw

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor..... County of... Umatilla
State of... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 15th day of November..... 1982
David H. Lumber by *Betty L. Shatto*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor *GPO-798-276
Date _____
Rec'd by _____
No. 82-136-B