

USDA-FOREST SERVICE

Index

File No. S-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. Sec 26

Cor.

No. N 1/16

T 35 R. 32E

R.D.

Ukiah

County

Umatilla

Merid. Willamette

N.F.

Umatilla

State

Oregon

CORNER DIAGRAM

T3S R32E

N 1/16

S27 S26

1982

PLS 1106



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Road #54 to road #5412, then West to road #010, then North to road #016, Northeast along road #016 1/4 mile then North to 100 feet South of bottom of draw, to corner. On North facing slope, in timber.

Signature

Wallin R. Wells

Title

PLS 1106

Division

Headquarters

Date

October 14, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 15" in ground surrounded with mound of stone. Set steel fence post, w/54-2 & 9 signs, East of corner.
 Cap marked:

T3S R32E
 N 1/16
 S27 | S26
 1982
 PLS 1106

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 11" dia. grand fir bears S71°E 38.0 ft. dist. marked: N 1/16 S26 BT.
 A 12" dia. spruce bears S 15½°W 22.5 ft. dist. marked: N 1/16 S27 BT.
 Painted blaze faces and 6" band around bearing trees red. Trees tagged with 54-3 and 54-9 signs.
 New BTS have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date _____ State Registration No. PLS 1106
 or Agency _____

Certified Cor. Record Prepared? Yes No _____ Filed At: Umatilla County Surveyor Office Date _____

REMARKS

Witnessed by: Leslie E. Wilson
Larry Henshaw

Index File No. S-17 T 3S R. 32E M. W.M. Tract or Surv. No. S 26 Cor. N 1/16