


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on 2 1/2" x 30" l. pipe 21" in ground, with mound of stone to cap, from which:

Steel fence posts South and West of corner, with 54-2 signs on both and 54-9 on one.

A 11" dia. red Fir bears S13°W 16.2 ft. dist. marked: NW 1/16 S26 BT.

A 15" dia. Grand Fir Bears S61°E 5.5 ft. dist. marked: NW 1/16 S26 BT.

Blaze faces and 6" band around bearing trees, painted red. Trees tagged with 54-3 and 9 signs. New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 18, 1982.

Cap marked:

T3S R32E
NW 1/16. S26
1982
PLS 1106

Witnessed by: Leslie E. Wilson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor..... County of.....Umatilla.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

Daniel H. Krauss by Betty L. Matto

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd ..y _____

No. 82-136-B