


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-13

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 1882. The original notes state that at the corner position a Pine 8" dia was marked for the corner on S W Slope from which:



A 4" dia. Tamarack bears N56°E 13 lks dist marked: 1/4S BT.
A 10" dia. Tamarack bears N67°W 44 lks dist marked: 1/4S BT.

No restoration appears in County Records.

Description of corner evidence found:

A 10" Tamarack Snag bears N67°W 44 lk dist tagged S67°E 44 lk dist. opened healed blaze to reveal scribing.

Description of monument and accessories I established to perpetuate the original location of this corner:


After opening bearing tree and finding scribing and using original bearing and distance I re-established the W 1/4 of S27 and set a 3" brass cap on 2 1/2" x 30" I. pipe 24" in ground with mound of earth from which:

A 7" dia. W. Fir bears N52°W 28.4 ft. dist. marked: 1/4S28 BT.
A 12" Red Fir bears N24°E 6.2 ft. dist. marked: 1/4 S27 BT.
A 6" band around bearing trees and blaze faces are painted red. Tagged trees with 54- 3 and 4 signs. New BTs have lower blaze, scribed BT with brass washer stamped PLS 1106 nailed flush. Set steel fence post with 54-4 sign on section line near corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of trees.

The corner was monumented on September 23, 1982

Cap marked:

Witnessed by: D.L. Kaufman PLS



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of... County Surveyor... County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the 15th day of December, 1982
David H. Thompson by Betty L. Shatto

RECEIVED BY Umatilla County Surveyor Date Rec'd by No. 82-136-B