

USDA-FOREST SERVICE

Index

File No. T-18

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. Sec 26

Cor.

No. CW 1/16

T 3S R. 32E

R.D.

Ukiah

County

Umatilla

Merid. Willamette


N.F.

Umatilla

State

Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES; ALSO HOW TO REACH CORNER

Road #54 to road #5412, then West to road #012, then N W on road #012 1/4 mile then North 700 ft. to corner, in small clearing on West facing slope. 300' N E of Carnes cabin.

Signature

William R. Wells

Title

PLS 1106

Division

Headquarters

Date

October 14, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 12" in ground with mound of stone to cap.

Set steel fence post with 54-2 and 9 signs, North of corner. Cap marked:

T3S R32E
W 1/16
C ——— C
S26
1982
PLS 1106

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 17" dia. P. Pine bears East 66.0 ft. dist. marked: CW 1/16 S26 BT.

A 11" dia. W. Fir bears S23 1/2°E 133.1 ft. dist. marked: CW 1/16 S26 BT.

Blaze faces and 6" bands around bearing trees were painted red. Trees tagged with 54-3 and 9 signs. New BTs have lower blazes, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W. R. Wells Title Surveyor Date 10/14/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date _____

REMARKS

Witnessed by: Leslie E. Wilson
Larry Henshaw

Index File No.

T-18

T.

3S

R.

32E

M.

W.M.

Tract or Surv. No.

Sec 26

Cor.

CW 1/16