


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-19

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in the ground, with mound of stone from which:

A 11" dia. Grand Fir bears N88°W 8.3 ft. dist. marked: C1/4 S26 BT.

A 14" dia. Tamarack bears N36°E 6.2 ft. dist. marked: C1/4 S26 BT.

A steel fence post, with 54-9 sign, North of corner.


Blaze faces and 6" band around bearing trees, painted red. Trees tagged with 54-3 and 9 signs. New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106, nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 14, 1982.

Cap marked:

Witnessed by: Leslie E. Wilson
Larry Henshaw



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
11106

Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

Daniel H. Krumbein (COUNTY OFFICIAL) *Betty L. Shatto* (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd -y _____
No. 82-136-B