

USDA-FOREST SERVICE

Index
File No. T-19

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

Tract or
Survey No. Sec 26 Cor. No. C 1/4

T 3S R. 32E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T3S R32E
C 1/4 . S26



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
Road #54 to road #5412, then West to road #012, then taking trail North down open ridge top to fence, then 100 ft North from fence and South edge of timber, then 250 ft East in thicket to corner.

Signature

Willie R. Webb

Title

PLS 1106

Division

Headquarters

Date

October 14, 1982

7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" brass cap on 2 1/2" x 30" I. pipe 24" in the ground with mound of stone.

Set steel fence post, with 54-9 sign, North of monument.

T3S R32E
C 1/4 . S26
1982
PLS 1106

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 11" dia Grand Fir bears N88°W 8.3 ft dist marked: C 1/4 S26 BT.

A 14" dia Tamarack bears N36°E 6.2 ft dist marked: C 1/4 S26 BT.

Blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54-3 and 9 signs.

New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date 10/14/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date _____

REMARKS

Witnessed by: Leslie E. Wilson
Larry Henshaw

Index File No.
T-19

T. 3S R. 32E M. W.M.

Tract or Surv. No.

Sec 26

Cor. C 1/4