


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-21

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner a 12" x 10" x 5" basalt stone was set on N.E. slope in mound of stone, marked 1/4 on W face from which:



A Pine 20" dia. bears S67°W 115 lks dist. marked 1/4S BT.

No record of restoration was found in County Records.

Description of corner evidence found:

A 12" x 12" x 6" basalt stone on slope with 1/4 marked on the W face, from which:

A 29" P. Pine bears S67°W - 76.5 ft. dist. (original BT with healed blaze).

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" x 30" I. pipe w/3" brass cap 21" in the ground with mound of stones and corner stone buried alongside. The monument is leaning slightly East due to a root, from which:

A 20" Red Fir bears S45°E 3.8 ft. dist. marked: 1/4 S25 BT

Blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54-3 & 4 signs where needed.


New BT has lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination.

Measured to center of BTs.

This corner was set on September 22, 1982.

Cap marked:



Witnessed by: D.L. Kaufman PLS

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of... County Surveyor... County of... Umatilla

State of... Oregon... I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

David H. Humber by Betty L. Shatto (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY Umatilla County Surveyor Date Rec'd - y No. 82-136-B