

USDA-FOREST SERVICE

Index File No. U-18

T 3S R. 32E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

Tract or Survey No. Sec 26 Cor. No. SW 1/16

CORNER DIAGRAM

T3S R32E

SW 1/16

S26



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
Road #54 to road #5412, then West to road #012, then North along road #012 approximately 1,000 ft. then 300 ft. West to corner. On open hillside on Easterly facing slope and 100 ft. West of drainage.

Signature

Title

Division

Headquarters

Date

*William R. Wells*

PLS 1106

October 14, 1982

7100-52-(3-68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 6" in ground, in mound of stone.  
 Set Steel fence posts with 54-2 signs on both and 54-9 sign on one, North and West of corner.  
 Cap marked:

T3S R32E  
 SW 1/16  
 S26  
 1982  
 PLS 1106

**ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A 19" dia. P. Pine bears N74°E 34.2 ft. dist. marked: SW 1/16 S26 BT.  
 A 15" dia. P. Pine bears S16°W 83.6 ft. dist. marked: SW 1/16 S26 BT.  
 blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54-3 and 9 signs.  
 New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W. R. Wells Title Surveyor Date 10/14/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla County Surveyor Office Date \_\_\_\_\_

**REMARKS**

Witnessed by: Leslie E. Wilson  
Larry Henshaw

Index File No.

U-18

T.

3S

R.

32E

M.

W.M.

Tract or Surv. No.

Sec 26

Cor.

SW 1/16

10

11

12

13