


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-15

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner a basalt stone 14" x 10" x 5" was set 10" in ground marked 1/4 on North face, from which:



A Pine 16" dia. bears North 212 lks dist. marked 1/4 S BT.
A Pine 40" dia. bears S38°W 176 lks dist. marked 1/4 S BT.

Remonumentation done in 1977 by BLM, see sheet 2 for record of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" I. pipe set in mound of stone, from which:

- A 33" P. Pine Snag bears S43°W 117.9 ft. dist. tagged N38°E 176 lk dist (old BT) open blaze.
- A 45" Fir Stump bears N1°W 139.4 ft. dist. 60° visible scribing (old BT)
- A 14" Fir bears N4°W 166.3 ft. dist. tagged S3°E 252 lk dist. - recent scribe
- A 18" Fir bears S35 1/2°W 149.7 ft. dist. tagged N36°E 227 1/2 lk dist. - recent scribe


Description of monument and accessories established to perpetuate the original location of this corner:

Set steel fence post, with 54-4 sign on section line near corner.
Painted blaze faces and 6" band around bearing trees red. Tagged trees with 54-3 & 4 signs where needed.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to the center of the bearing trees.

The corner was maintained September 23, 1982.

Cap is standard BLM cap marked:

Witnessed by: D.L. Kaufman PLS



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of...County Surveyor... County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office
for record on the... 15... day of... December... 1982
David H. Krumborn by Betty L. Slatt
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-136-B

History of 1977 BLM Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of secs. 27 and 34, monumented with the original unmarked basalt stone, 14 x 10 x 5 ins., firmly set 4 ins. in the ground, from which the remains of the original bearing trees:

A sawed Pine Stump, 45 ins. diam., bears North, 212 lks. dist., no marks visible.

A decayed Pine Snag, size indeterminate, bears S. 43 $\frac{1}{2}$ ° W., 178 lks. dist., with fragmentary scribe marks visible on opened blaze. (Record, S. 38° W., 176 lks.)

At the corner point

Set an iron post, 28 ins. long, 2 $\frac{1}{2}$ ins. diam., 18 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S R32E
1/4 $\frac{S27}{S34}$
1977

from which new bearing trees

A Grand Fir, 13 ins. diam., bears N. 3° W., 252 lks. dist., mkd. 1/4 S27 BT.

A Fir, 17 ins. diam., bears S. 36° W., 227 $\frac{1}{2}$ lks. dist., mkd. 1/4 S34 BT.

Deposit corner stone alongside iron post.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-136-B