

USDA-FOREST SERVICE

Index File No. V-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 27 Cor. No. S 1/4

T 3S R. 32E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T3S R32E

1/4 S27
S34



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" I. pipe in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND.

A 33" P.Pine Snag brs S43°W117.9 ft dist tagg N38°E176lk dist (old BT) open blaze.

A 45" F.Stump brs N1°W139.4 ft dist - no visible scribing.

A 14" R.Fir brs N4°W166.3 ft dist tagg S3°E 252 lk dist-newly scribed.

A 18" R.Fir brs S35 1/2°W149.7 ft dist tagg N36°E117 1/2 lk dist-newly scribe.

PHOTO IDENTIFICATION DATA

Photo No. 616140 680-297

Filed At. Umatilla Nat. Forest

Object Ident. Trees

Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Pearson Creek Road #54 to road #5412, West 1 1/2 miles, then North 100 ft to corner.

Signature

William R. Wells

Title

PLS 1106

Division

Headquarters

Date

September 23, 1982

7100-52-(3,68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post, with 54-4 sign, on section line near corner.
Cap is standard BLM. Cap marked:

T3S R32E
1/4 $\frac{S27}{S34}$
1977

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted red 6" band around bearing trees and blaze faces. Tagged trees with 54-3 and 54-4 signs where needed.

Work Done By. W.R. Wells Title Surveyor Date 9/23/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by: D.L. Kaufman PLS

Index File No.
V-15

T. 3S R. 32E M. W.M.

Tract or Surv. No. Sec 27

Cor. S 1/4