

USDA-FOREST SERVICE

Index

File No. V-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. Sec 26

Cor.

No. SW

T 3S R. 32E

R.D.

Ukiah

County

Umatilla

Merid. Willamette

N.F.

Umatilla

State

Oregon

CORNER DIAGRAM

T3S	R32E
S27	S26
S34	S35



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" I. pipe set in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

- A 32" P Pine brs S72°W13.0 ft tagg N70°E 20 lk-old BT open blaze.
- A 38" P Pine brs N80°W75.9 ft tagg S79°E 116 lk-old BT healed blaze.
- A 26" P Pine brs S49 1/2°E60.3 ft tagg N47 1/2°W 91 lk-old BT part.heal.bl.
- A 40" P Pine brs N86°E81.9 ft tagg S86°W 122 lk-old BT healed blaze

PHOTO IDENTIFICATION DATA

Photo No. 616140 680-297

Filed At. Umatilla Nat. Forest

Object Ident. Trees

Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Pearson Creek Road #54 to the intersection of road #5412, go West 1 mile then South 120 ft to corner.

Signature

William R. Wells

Title

PLS 1106

Division

Headquarters

Date

September 22, 1982

7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post with sign 54-4 on section line near corner.
Cap is standard BLM cap.

Cap marked:

T3S R32E
S27 | S26
S34 | S35
1977

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted 6" band around bearing trees and blaze faces red. Tagged trees with 54-3 and 4 signs where needed.

Work Done By W.R. Wells Title Surveyor Date 9/22/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by: D.L. Kaufman PLS

Index File No.
V-17

T. 3S R. 32E M. W.M.

Tract or Surv. No. Sec 26

Cor. SW