


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-19

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner a granite stone 18" x 14" x 3" was set 12" in ground on East slope marked 1/4 on North face.



No trees, raised mound of stone along-side in lieu of pits.

No restoration appears in County Records.

Description of corner evidence found:

Found 23" x 16" x 3" granite stone marked 1/4, lying on its side.

From location of stumps around corner stone it is evident it has not been disturbed, but has just fell over.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" I. pipe 24" in the ground with mound of earth to cap. (Buried stone along-side monument) from which:

A RM bears S48 1/2° E 30.73 ft. dist. marked T3S R32E S35 RM.

A RM bears N10 1/2° E 26.80 ft. dist. marked T3S R32E S26 RM.

Reference monuments were set because no live trees were within limits.


Set steel fence posts, w/54-4 signs, on section line near corner.

Used steel tape and magnetic compass 19 3/4° declination.

Reference monument example:
Reference monuments are 2 1/2" x 30" iron pipes with 2 1/2" brass caps set 24" in ground and surrounded with a mound of earth.



Brass cap at corner marked:



Corner set on September 29, 1982.
Witnessed by: Leslie E. Wilson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of _____ County Surveyor _____ County of _____ Umatilla

State of _____ Oregon _____ I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

Daniel H. Kussman by *Betty L. Shatto*

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-136-B