

USDA-FOREST SERVICE

Index

File No. V-21

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 26 Cor. No. SE Cor

T 3S R. 32E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T3S	R32E
S26	S25
S35	S36



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" x 28" l. pipe protruding 3" above mound of stone. Cap is standard BLM cap.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 16" dia Pine Snag bears N76¹/₂°W 48.0 ft dist (burnt out blaze)
A 8" dia L.P. Pine bears S85°W 6.8 ft dist (burnt out blaze)

PHOTO IDENTIFICATION DATA

Photo No. 616140 680-287

Filed At. Umatilla Nat. Forest

Object Ident. Stone and Tree

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Road #54 to road #5425, West to road #020, then North on #020 approximately 5/8 mi. to Skid Trail to South then South on Skid Trail approximately 600 ft then West 200 ft corner on knob in Granite Meadows clear cut.

Signature

Willie R. Wells

Title

PLS 1106

Division

Headquarters

Date

September 29, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post with 54-4 sign on section line near corner.
 Cap is standard BLM. Cap marked:

T3S R32E
 S26 | S25
 S35 | S36
 1977

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE.

A RM bears S55 $\frac{1}{2}$ ° E 40.37 ft dist marked T3S R32E S36 RM. Example
 A RM bears S38 $\frac{1}{2}$ ° W 30.36 ft dist marked T3S R32E S35 RM. R.M. Cap:
 A RM bears N38 $\frac{1}{2}$ ° E 42.65 ft dist marked T3S R32E S25 RM.
 A RM bears N55 $\frac{1}{2}$ ° W 31.68 ft dist marked T3S R32E S26 RM.
 All RM's are set 24" in ground with mound of stone and steel fence posts
 with 54-4 signs, nearby.

T3S R32E
 S35
 R.M. (dist)
 1982
 PLS 1106

Work Done By W.R. Wells Title Surveyor Date 9/29/82 State Registration No. or Agency PLS 1106

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla County Surveyor Office Date _____

REMARKS

Witnessed by: L.E. Wilson

Index File No. V-21 T. 3S R. 32E M. W.M. Tract or Surv. No. Sec 26 Cor. SE Cor