


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-5

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 1882. The original notes state that at the corner position a post 5" dia x 4' long was set with SE and NE faced, 2 ft in ground, on East slope from which:



A 8" dia Fir bears N76°E 79 lk dist.
A 7" dia Pine bears S24°E 58 lk dist.

Description of corner evidence found:

A 12" dia Fir Stump bears N76°E 52.14 ft dist tagged S76°W 52.1 ft dist (oldBT scribing visible)

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 22" in ground with mound of stone from which:


A 10" Grand Fir bears S50°E 6.8 ft dist marked: T3S R32E S32 CC BT.
A 10" Grand Fir bears N15 1/2°E 37.5 ft dist marked: T3S R32E S29 CC BT.

Blaze faces and 6" band around bearing trees painted red. Tagged trees with 54-3 and 4 signs. Each new BT has lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.
A steel fence post with 54-4 sign, 3.7 ft East of corner.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of trees.

Corner monumented on September 29, 1982.

Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

This corner is 0.04' East of the range line.

Office of..... County Surveyor..... County of..... Umatilla
Oregon.....
I hereby certify that the within instrument was filed in this office
for record on the 15th day of December....., 1982
David H. Krumbein (COUNTY OFFICIAL) *Dolly L. Shatto* (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-137-B