

A-17


History of original corner establishment:

The exterior lines of Township 3 South, Range 33 East were originally established by Rufus L. Moore under Contract No. 451 dated June 12, 1882.

Page 17 of the original notes state that at the corner, a basalt stone, 14"x8"x7", buried 10" in ground was set with a mound of stone from which:

- A 10" pine bears S51°W 110 LK (72.6 ft) marked T3S R33E S3 BT
- A 6" fir bears N13°E 72 LK (47.5 ft) marked T2S R33E S35 BT
- A 6" fir bears N20°W 59 LK (38.9 ft) marked T2S R33E S34 BT

Note: Township 2S Range 33E was later surveyed, resulting in the section configuration shown.



No record of subsequent re-monumentation found in County records.

Description of corner evidence found:

No evidence of original corner found.

- A 12" fir with open blaze and no visible scribing bears N13°E 47.5 ft to center tree.
- A 12" fir with healed blaze bears N 20°W 38.9 ft to center tree.
- A down and rotten pine (completely decayed) bears S51°W 72.5+ ft to center tree.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 10 inches in ground and surrounded with a mound of stones to within 6" of the top of cap.

Set steel fence post 4'+ East of monument on Township line and attached signs 54-2 and 54-4.

Established 2 new BT's: A 18" fir bears S62½°W 54.1 ft. scribed T3S R33E S3 BT, a 17½" fir bears S32°E 117.4 ft. scribed T3S R33E S2 BT.

New BTS have a lower blaze scribed BT with brass washer stamped PLS 1106 nailed flush. Attached sign 54-3 and 54-4 and painted red ring around all BT's.


Used steel tape and magnetic compass with 19½° east variation. Measured to center of BT's. See Map of Survey

This Corner Set June 28, 1979

Witnesses: Greg Flowers, L.S.I.T
Brent Reynolds

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of... County Surveyor... County of... Union

State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the... day of... 19...

..... by (COUNTY OFFICIAL) (DEPUTY)

S-68-m
A-17
* GPO - 798-276