


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. A-7

History of original corner establishment:

In 1882, under G.L.O. contract No. 451, Rufus S. Moore set a post 3 ft long 3 ins square 24 ins in ground for 1/4 cor. marked 1/4 Sec. on N. face, from which a pine 4 ins. dia. bears S64°W, 91 lks (60.1 ft) dist. marked 1/4S BT. A Pine 18 ins. dia. bears N42°E, 110 lks (72.6ft) dist. marked 1/4S BT.



Description of corner evidence found:


Could find no evidence of the original post.

Found Dead Lodge Pole Pine 10" dia. with opened blaze and visible scribing "1/4S" for SW BT and a Ponderosa Pine (live) 25" dia. with opened blaze and visible scribing "1/4S" for NE BT. Measured record dist. from both BT's. At intersection point set up staff compass and shot bearings to old BT's, Ponderosa Pine is N42°E and Lodge Pole Pine is S46°W which leads me to believe the original surveyor transposed his numbers in the SW bearing.

Description of monument and accessories established to perpetuate the original location of this corner:

At point of intersections set 2 1/2"x30" galvanized pipe with brass cap stamped:


Set pipe 22" in ground with mound of stone to cap.



Bearing Trees:

Old: Dead Lodge Pole Pine 10" dia. bears S46°W, 60.1 ft, with visible scribing "1/4S".
 A Live Ponderosa Pine 25" dia. bears N42°E, 72.6 ft, with visible scribing "1/4S".
 New: A White Fir 12" dia. bears S80°E, 14.0 ft, scribed 1/4 S5 BT.
 A Douglas Fir 12" dia. bears S26°W, 29.5 ft, scribed 1/4 S5 BT.

Attached 54-3 & 54-4 signs to all BT's. Attached brass washer stamped LS1294 to foot blaze of new BT's. Painted blazes and 6" band around both BT's red. Attached 54-4 sign to metal post 5 ft. East of corner.



I hereby certify the above corner monument was re-established as herein described on July 31, 1980.

Witnesses: R. Orton
 L. Huntsman
 D. Allen

Office of..... County Surveyor..... County of..... Umatilla.....
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... December..... 19..... 80
 David..... Huntsman by Betty Shuttle.....
 (COUNTY OFFICIAL) (DEPUTY)