


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-13

History of original corner establishment:

In 1882, under GLO Contract No. 451, Rufus S. Moore set a post, from which an 8" Pine bears N63°W, 31 lks.; a 12" Pine bears N13°E, 31 lks.; a 26" Tamarack bears S35°E, 9 lks.; and an 11" Pine bears S43°W, 19 lks.



Description of corner evidence found:

No corner monument was found.

Bearing Trees Found:

A 23" W. Larch bearing S35°E, 5.9 ft. to face of blaze,
 A 6.4 ft. to middle of tree, scribed "S 15".

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2"x30" aluminum capped aluminum pipe, rising 7", stamped:

New BT's:

- A 7" D. Fir bearing N56°W, 18.1 ft.,
scribed T3S R33E S9 BT.
- A 6" D. Fir bearing N5 1/2°E, 10.7 ft.,
scribed T3S R33E S10 BT.
- A 10 1/2" D. Fir bears S51°E, 48.5 ft.,
scribed T3S R33E S15 BT.
- A 9 1/2" D. Fir bears S7 1/2°W, 16.7 ft.,
scribed T3S R33E S16 BT.

T3S R33E
 S9 | S10
 S16 | S15
 RLS 1848
 1984

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6 March, 1982. Set metal fence post 4 ft. north of corner.

Compass Declination: 19 1/2°E

Witness: G. Arrand

From the 1/4 corner between 15 & 16, which falls along the north side of USFS Rd. 5427, go .4 mi. north to beginning of razorback ridge bearing N10°W. Follow ridge 400 ft. Corner is approx. 450 ft. down the easterly slope.

I hereby certify the above described corner monument and/or accessories was established as described on June 9, 1984.



Office of... Surveyor County of... Umatilla
 State of... Oregon I hereby certify that the within instrument was filed in this office
 for record on the... 10th day of... July 19... 84
David Truman (COUNTY OFFICIAL) by Betty Cochran (DEPUTY)