


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Z-15

History of original corner establishment:

In 1882, under GLO Contract No. 410, George S. Pershin set a stone 17x8x6, from which an 11" Fir bears N60°E, 37 lks. and a 12" Pine bears S3°W, 8 lks.



Description of corner evidence found:

Found original stone 14x8x6 with "1/4" on north face, firmly in place.

Bearing trees found:

An 18 1/2" Fir bears N60°E, 5.6 ft. to middle of tree, blaze healed.
A 13 1/2" P. Pine bears S8°W, 25.2 ft. to middle of tree, scribing visible: "1/4S".

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2"x30" aluminum capped aluminum pipe rising 12" in mound with original stone in hole on north side, Cap stamped:

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March, 1982.

Compass Declination: 19 1/2°E
Witness: G. Arrand

Set metal fence post 4 ft. north of corner.

From 2110-220 northwesterly on 2110-048 .6 mi. to a 54-5 location poster on a 6" Fir on the south side of the road. Corner is 350 ft. south.

I hereby certify the above described corner monument and/or accessories was established as described on June 8, 1984.



Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 10th day of July, 1984
David K. Rumbert by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)