


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index-File No. Z-19

History of original corner establishment:

In 1882, under GLO Contract No. 410, George S. Pershin set a post, from which a 16" Fir bears North, 70 lks. and an 18" Pine bears S56°W, 14 lks.



Description of corner evidence found:

No corner monument found.

Bearing trees found:

- A 25" Fir bears N7°E, 46.6 ft., blaze healed.
- A 24" W. Larch (called pine in original notes) bears S56°W, 9.8 ft. to center of tree, blaze healed, dead standing.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2"x30" aluminum capped aluminum pipe rising 6", stamped:

New BT:

An 11" Fir bears S68°E, 11.7 ft., scribed 1/4 S2 BT.

T3S R33E

1/4  $\frac{S35}{S2}$

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March 1982.

T4S  
RLS 1848  
1984

Compass Declination: 19 1/2°E

Witness: G. Arrand

Set a metal fence post 4 ft. north of corner.

From 2110-230, follow 2110-232 southeasterly to the end of the meadow, Corner is east across meadow and 150 ft. into the woods.

I hereby certify the above described corner monument and/or accessories was established as described on June 8, 1984.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*B. A. Sutton*  
OREGON  
JULY 13, 1979  
B. A. SUTTON  
1848

Office of Surveyors ..... County of Umatilla  
 State of Oregon ..... I hereby certify that the within instrument was filed in this office  
 for record on the 10<sup>th</sup> day of July ..... 1984  
David R. Smith by Billy Cochran  
 (COUNTY OFFICIAL) (DEPUTY)

2-19

84-79-m