


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. 7-25

History of original corner establishment:

In 1881, under Glo Contract No. 410, George S. Pershin set a stone 18x12x5, from which a 12" Pine bears N74°W, 23 lks.; a 6" Pine bears N38°E, 80 lks.; a 16" Pine bears S58°E, 48 lks.; and a 15" Pine bears S50°W, 13 lks.



Description of corner evidence found:

Found original stone 18x12x5 with 6 notches on the north & 6 notches on the south & 6 notches on the west.

Bearing Trees Found:

- A 15.2" dead standing P. Pine bearing N70°W, 22.2 ft., scribed "T4S R33E S1 BT".
- A 20" dead standing P. Pine bearing S50°W, 8.6 ft., blazed.
- A 19.5" dead standing P. Pine bearing S58°E, 31 ft., scribed "T3S R34E S6 BT".

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3 1/4" aluminum cap on 2 1/2"x30" aluminum pipe, stamped: rising 10" in mound. Buried original stone along north side of mound.

New BT's:

- A 5.5" D. Fir bearing N42°W, 29.1 ft., scribed "T3S R33E S36 BT".
- A 9.7" D. Fir bearing N54°E, 66.6 ft., scribed "T3S R33 1/2E S34 BT".
- A 12.8" D. Fir bearing S70°W, 112.1 ft., scribed "T4S R33E S1 BT".

T3S
R33E R33 1/2E
S36
S1 S34
1983
RLS 1848

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March, 1982.

Compass Declination:
19 1/2°E
Witness: N. Petz

From the south line of S36 go north on 2110-320 400 ft. to an unmarked road that continues northerly and easterly, 1/2 mi. to the creek crossing. Take the right fork across the creek, up the hill southeasterly 1/4 mi. to another fork. Take right fork 3/8 mi. Take next right fork through an opening in the woods, to a clearing. Continue SE'ly 1/4 mi. Take left fork east 350 ft. to corner.



I hereby certify the above described corner monument and/or accessories was established as described on Sept 13, 1983.

Office of Surveyor..... County of Umatilla
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 10th day of July..... 1984
David Krumbein by Beth Cochran
 (COUNTY OFFICIAL) (DEPUTY)