

OREGON CORNER RESTORATION FORM

SECTION 1 TOWNSHIP 4 NORTH RANGE 27 EAST A-25
 COUNTY : UMATILLA DATE 10-2002

CORNER DESIGNATION

NORTH EAST CORNER

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNCOVERED
- SURVEYED IN
- REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

ORIGINALLY SURVEYED BY HAFT IN 1860, CONTRACT #93.
 DEPENDENT SURVEY BY GOULD IN 1941.
 KRUMBELN SURVEY FOR UMATILLA COUNTY 1980.
 EDWARDS 1994 SURVEY FOR O.D.O.T., FOUND & RESET GOULD MONUMENT.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND A 3 1/2" BRASS CAP ON A GALVANIZED PIPE STAMPED AS BELOW.
 A 2 1/2" BRASS CAP STAMPED 1980 LS 933 BEARS S 89°47'06" W 49.00 FEET.

MONUMENT DETAIL



NAD 83/91
 OREGON STATE PLANE
 INTERNATIONAL FEET
 803413.9264
 8489427.6477

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

NA

NEW ACCESSORIES FROM WHICH

A 5/8"X30" IRON REBAR WITH PLASTIC CAP #951 BEARS N 86°38'21" E 64.95 FEET.
 A 5/8"X30" IRON REBAR WITH PLASTIC CAP #951 BEARS S 87°35'09" W 133.34 FEET.
 AN ALUMINUM TAG #951 ON A POWER POLE BEARS S 10°28'09" W 229.29 FEET.

COMPASS DEC.

SURVEYOR'S SEAL

LOCATION AND COMMENTS

FROM WESTERLY END OF BRIDGE ROAD, CROSS I-82 TO FRONTAGE ROAD, AND FOLLOW FRONTAGE ROAD NORTHEASTERLY TO THE RANGE LINE. THEN GO NORTH ALONG GRAVEL ROAD 1.35 MILES TO THE SECTION CORNER.

FIRM/AGENCY

EDWARDS SURVEYING
 P.O. BOX 763
 HERMISTON, OREGON 97838

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

PARTY CHIEF

CURTIS FAVOREL

G. Dennis Edwards

NOTES

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 9 5 1

WITNESS

RICK SMITH

RECEIVED BY RENEWS 12/31/2003

Umatilla County Surveyor

Date 3-03

Rec'd By *JK*

Na 03-50-g