

CORNER RESTORATION FORM

Township 4N Range 28E Section 7, 8 County UMATILLA
 State OREGON Date 4-4-2019 Number G-5

Corner Designation: 7, 8

Previous Renewals ORIGINAL SOURCE OF CORNER

ORIGINALLY SURVEYED IN 1860 BY HAFT UNDER CONTRACT #93. HE SET POST IN MOUND WITH TRENCH, MADE PITS AND DEPOSITED A PINT OF CHARCOAL.

Accessories Found: _____

FOUND 5/8" IRON REBAR W/YELLOW PLASTIC CAP DAMAGED AT NE CORNER RR TIE, S89°40'W, 20.13'

FOUND STOP SIGN POST, SW CORNER, N88°05'E, 39.96'

Condition Report Only

- Not Found
- Renewed
- Surveyed In
- Referenced

MONUMENT DETAIL

Found Set



1" SMOOTH IRON ROD

NORTHING: 795439.24
 EASTING: 8494506.81

Monument & Accessories Set (Procedure and Description) _____

FOUND 1" SMOOTH IRON ROD 4" BELOW AC. AS PER COUNTY SURVEY I-46-B.

SET 5/8" x 10" REBAR W/RED PLASTIC CAP PLUS 61420, 6" DEEP, .8" EAST OF RR TIE, S32°35'W, 38.21'

SET 1 1/2" STEEL WASHER MARKED 61420, IN POWER POLE W/MAG NAIL APPROX. 2" ABOVE GRADE, S29°06'E, 47.93'

Sketch of Monument, Accessories and General Area

REGISTERED PROFESSIONAL LAND SURVEYOR
Lance Clark King
OREGON
MAY 10, 2011
LANCE CLARK KING
61420

RENEWALS: 6/30/2021

Agency: CK3, LLC
 945 W. ORCHARD
 HERMISTON OREGON 97838
 OFFICE: 541-567-2345
 FAX: 541-567-2305
 WEB: CK3LLC.NET
 Field Book # 0-325

COUNTY SURVEYOR RECORDING INFO

Received _____
 Filled _____
 Survey No. _____
 Drawing No. _____
 Index No. G-5

19-080-C