

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

N-13

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

N E Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

In 1981, Krumbein set Brass Cap at location of a RR spike in Mon. Box. (Origin unknown).

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found at corner.

Found a 2 1/2" Brass Cap W.C. stamped 43.91 1983 LS 933, Bears N 55° 20' 49" W 43.91 feet, inside Monument Box.

Found a 2 1/2" Brass Cap W.C. stamped 50.89 1983 LS 933, Bears S 47° 58' 58" W 50.66 feet.

Found a 5/8" Iron rod W.C. O.S.H.D. Bears S 89° 20' 52" E 28.00 feet.

MONUMENT DETAIL

SKETCH

MONUMENT SET (PROCEDURES AND DESCRIPTION)

I set P.K. nail in centerline of heavily traveled North bound lane of Buttercreek Highway.

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 62° 41' 55" W 38.91 feet with Bearing Object sign attached.

An Alum. tag #951 in Power pole Bears S 46° 21' 30" W 47.65 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951 Bears S 89° 20' 52" E 40.00 feet. Drove steel fence post with Witness Corner sign attached.

LOCATION & COMMENTS

Corner is at the intersection of Buttercreek Hwy. and Minnehaha Road.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C